



PROJECT:

ADDRESS:

| SR # | CSI SECT       | DESCRIPTION                                                        | QUANTITY | WASTAGE (10%) | QTY WITH WASTAGE | UNIT OF MEASUREMENT | UNIT COST | TOTAL ITEM COST | TOTAL TRADE COST |
|------|----------------|--------------------------------------------------------------------|----------|---------------|------------------|---------------------|-----------|-----------------|------------------|
|      |                |                                                                    |          |               |                  |                     |           |                 |                  |
|      | <b>DIV. 06</b> | <b>WOOD, PLASTIC AND COMPOSITES</b>                                |          |               |                  |                     |           |                 | \$ -             |
|      |                | <b>Wooden Posts</b>                                                |          |               |                  |                     |           |                 |                  |
| 1    |                | 9'-11 1/4" Long, 3 1/2"x 5 1/4" PSL Post                           | 1        | 0%            | 1                | EA                  | \$        | -               |                  |
| 2    |                | 9'-11 1/4" Long, 5 1/4"x 5 1/4" PSL Posts                          | 4        | 0%            | 4                | EA                  | \$        | -               |                  |
| 3    |                | 9'-11 1/4" Long, 6"x6" Pressure Treated Posts                      | 4        | 0%            | 4                | EA                  | \$        | -               |                  |
| 4    |                | 9'-11 1/4" Long, 3 1/2"x 5 1/4" PSL Posts                          | 1        | 0%            | 1                | EA                  | \$        | -               |                  |
| 5    |                | 9'-11 1/4" Long, 5 1/4"x 5 1/4" PSL Posts                          | 4        | 0%            | 4                | EA                  | \$        | -               |                  |
| 6    |                | 06p: 9'-11 1/4" Long, 3 1/2"x3 1/2" PSL Posts                      | 3        | 0%            | 3                | EA                  | \$        | -               |                  |
|      |                | <b>Structural Lumber</b>                                           |          |               |                  |                     |           |                 |                  |
| 7    |                | 10'-0" Long, 1 3/4" x 11 7/8" Laminated Veneer Lumber Flush Beams  | 3        | 0%            | 3                | EA                  | \$        | -               |                  |
| 8    |                | 11'-10" Long, 2x10 SPF #2 Beams                                    | 4        | 0%            | 4                | EA                  | \$        | -               |                  |
| 9    |                | 12'-6" Long, 1 3/4" x 11 7/8" Laminated Veneer Lumber Flush Beams  | 2        | 0%            | 2                | EA                  | \$        | -               |                  |
| 10   |                | 12'-8" Long, 1 3/4" x 11 7/8" Laminated Veneer Lumber Flush Beams  | 6        | 0%            | 6                | EA                  | \$        | -               |                  |
| 11   |                | 13'-10" Long, 1 3/4" x 11 7/8" Laminated Veneer Lumber Flush Beams | 3        | 0%            | 3                | EA                  | \$        | -               |                  |
| 12   |                | 13'-3" Long, 1 3/4" x 11 7/8" Laminated Veneer Lumber Flush Beams  | 3        | 0%            | 3                | EA                  | \$        | -               |                  |
| 13   |                | 14'-8" Long, 1 3/4" x 11 7/8" Laminated Veneer Lumber Flush Beams  | 2        | 0%            | 2                | EA                  | \$        | -               |                  |
| 14   |                | 2"x6" Roof Over Hang Lumbers                                       | 17       | 0%            | 17               | EA                  | \$        | -               |                  |
| 15   |                | 2'-0" Long, Roof Trusses                                           | 5        | 0%            | 5                | EA                  | \$        | -               |                  |
| 16   |                | 21'-0" Long, 1 3/4" x 11 7/8" Laminated Veneer Lumber Flush Beams  | 2        | 0%            | 2                | EA                  | \$        | -               |                  |
| 17   |                | 21'-5" Long, 1 3/4" x 11 7/8" Laminated Veneer Lumber Beams        | 2        | 0%            | 2                | EA                  | \$        | -               |                  |

|    |                                                                    |    |    |    |    |    |   |
|----|--------------------------------------------------------------------|----|----|----|----|----|---|
| 18 | 21'-5" Long, 1 3/4" x 11 7/8" Laminated Veneer Lumber              | 2  | 0% | 2  | EA | \$ | - |
| 19 | 29'-0" Long, 2"x8" Bolted Ledger                                   | 1  | 0% | 1  | EA | \$ | - |
| 20 | 29'-8" Long, 4"x8" Western Red Cedar Beams                         | 1  | 0% | 1  | EA | \$ | - |
| 21 | 3'-5" Long, 1 3/4" x 11 7/8" Laminated Veneer Lumber               | 6  | 0% | 6  | EA | \$ | - |
| 22 | 40'-10" Long, 1 3/4" x 11 7/8" Laminated Veneer Lumber Flush Beams | 2  | 0% | 2  | EA | \$ | - |
| 23 | 4'-2" Long, 1 3/4" x 11 7/8" Laminated Veneer Lumber Beams         | 2  | 0% | 2  | EA | \$ | - |
| 24 | 4'-6" Long, 2x10 SPF #2 Beams                                      | 4  | 0% | 4  | EA | \$ | - |
| 25 | 257'-4" Long, 5/4x8 Trim Board                                     | 1  | 0% | 1  | EA | \$ | - |
| 26 | 6'-10" Long, 1 3/4" x 11 7/8" Laminated Veneer Lumber Flush Beams  | 2  | 0% | 2  | EA | \$ | - |
| 27 | 7'-6" Long, 1 3/4" x 11 7/8" Laminated Veneer Lumber Flush Beams   | 2  | 0% | 2  | EA | \$ | - |
|    | <b>Headers</b>                                                     |    |    |    |    |    |   |
| 28 | 1'-9" Long, 2"x8" SPF Headers                                      | 8  | 0% | 8  | EA | \$ | - |
| 29 | 2'-0" Long, 2"x8" SPF Headers                                      | 4  | 0% | 4  | EA | \$ | - |
| 30 | 2'-10" Long, 2"x7" SPF Headers                                     | 4  | 0% | 4  | EA | \$ | - |
| 31 | 2'-10" Long, 2"x8" SPF Headers                                     | 4  | 0% | 4  | EA | \$ | - |
| 32 | 2'-11" Long, 2"x8" SPF Headers                                     | 6  | 0% | 6  | EA | \$ | - |
| 33 | 2'-3" Long, 2"x8" SPF Headers                                      | 2  | 0% | 2  | EA | \$ | - |
| 34 | 2'-6" Long, 2"x8" SPF Headers                                      | 12 | 0% | 12 | EA | \$ | - |
| 35 | 2'-7" Long, 2"x8" SPF Headers                                      | 8  | 0% | 8  | EA | \$ | - |
| 36 | 2'-8" Long, 2"x8" SPF Headers                                      | 4  | 0% | 4  | EA | \$ | - |
| 37 | 2'-9" Long, 2"x8" SPF Headers                                      | 6  | 0% | 6  | EA | \$ | - |
| 38 | 3'-10" Long, 2"x8" SPF Headers                                     | 2  | 0% | 2  | EA | \$ | - |
| 39 | 3'-3" Long, 2"x8" SPF Headers                                      | 8  | 0% | 8  | EA | \$ | - |
| 40 | 4'-3" Long, 2"x8" SPF Headers                                      | 8  | 0% | 8  | EA | \$ | - |
| 41 | 4'-8" Long, 2"x7" SPF Headers                                      | 2  | 0% | 2  | EA | \$ | - |
| 42 | 5'-0" Long, 2"x7" SPF Headers                                      | 2  | 0% | 2  | EA | \$ | - |
| 43 | 5'-0" Long, 2"x8" SPF Headers                                      | 2  | 0% | 2  | EA | \$ | - |
| 44 | 5'-3" Long, 2"x7" SPF Headers                                      | 2  | 0% | 2  | EA | \$ | - |
| 45 | 6'-4" Long, 2"x8" SPF Headers                                      | 2  | 0% | 2  | EA | \$ | - |
| 46 | 9'-10" Long, 3 1/4" x9 1/4" Laminated Headers                      | 2  | 0% | 2  | EA | \$ | - |
|    | <b>Joists, Rafters and Trusses</b>                                 |    |    |    |    |    |   |

|                              |                                                    |       |     |       |    |    |   |
|------------------------------|----------------------------------------------------|-------|-----|-------|----|----|---|
| 47                           | 11'-4" Long, 11 7/8" TJI Wood Joists               | 2     | 0%  | 2     | EA | \$ | - |
| 48                           | 13'-0" Long Girder Trusses                         | 2     | 0%  | 2     | EA | \$ | - |
| 49                           | 13'-0" Long, Roof Trusses                          | 22    | 0%  | 22    | EA | \$ | - |
| 50                           | 13'-6" Long, 2"x8" Rafters                         | 6     | 0%  | 6     | EA | \$ | - |
| 51                           | 14'-0" Long, Roof Trusses                          | 23    | 0%  | 23    | EA | \$ | - |
| 52                           | 14'-8" Long, Roof Trusses                          | 22    | 0%  | 22    | EA | \$ | - |
| 53                           | 15'-10" Long, 11 7/8" TJI Wood Joists              | 10    | 0%  | 10    | EA | \$ | - |
| 54                           | 17'-0" Long, Roof Trusses                          | 16    | 0%  | 16    | EA | \$ | - |
| 55                           | 19'-10" Long, 11 7/8" TJI Wood Joists              | 41    | 0%  | 41    | EA | \$ | - |
| 56                           | 21'-5" Long, 11 7/8" TJI Wood Joists               | 26    | 0%  | 26    | EA | \$ | - |
| 57                           | 24'-11" Long Girder Truss                          | 1     | 0%  | 1     | EA | \$ | - |
| 58                           | 26'-0" Long, Roof Trusses                          | 11    | 0%  | 11    | EA | \$ | - |
| 59                           | 26'-9" Long, Roof Trusses                          | 4     | 0%  | 4     | EA | \$ | - |
| 60                           | 3'-10" Long, 11 7/8" TJI Wood Joists               | 1     | 0%  | 1     | EA | \$ | - |
| 61                           | 40'-10" Long Girder Trusses                        | 2     | 0%  | 2     | EA | \$ | - |
| 62                           | 41'-3" Long, Roof Trusses                          | 8     | 0%  | 8     | EA | \$ | - |
| 63                           | 41'-3" Long Girder Truss                           | 1     | 0%  | 1     | EA | \$ | - |
| 64                           | 4'-4" Long, Roof Trusses                           | 9     | 0%  | 9     | EA | \$ | - |
| 65                           | 8'-6" Long, 9 1/2" TJI Joists                      | 3     | 0%  | 3     | EA | \$ | - |
| 66                           | 7'-2" Long Girder Trusses                          | 2     | 0%  | 2     | EA | \$ | - |
| 67                           | 9'-6" Long Girder Truss                            | 1     | 0%  | 1     | EA | \$ | - |
| <b>Wall Studs</b>            |                                                    |       |     |       |    |    |   |
| 68                           | 2"x4" Wood Studs                                   | 2,829 | 10% | 3,112 | LF | \$ | - |
| 69                           | 2"x6" Wood Studs                                   | 3,268 | 10% | 3,595 | LF | \$ | - |
| <b>Top and Bottom Plates</b> |                                                    |       |     |       |    |    |   |
| 70                           | 2"x4" Top Plates                                   | 439   | 10% | 483   | LF | \$ | - |
| 71                           | 2"x4" Bottom Plates                                | 439   | 10% | 483   | LF | \$ | - |
| 72                           | 2"x6" Top Plates                                   | 497   | 10% | 547   | LF | \$ | - |
| 73                           | 2"x6" Bottom Plates                                | 209   | 10% | 230   | LF | \$ | - |
| 74                           | 2"x6" Mudsill                                      | 288   | 10% | 316   | LF | \$ | - |
| <b>Plywood Sheathing</b>     |                                                    |       |     |       |    |    |   |
| 75                           | 3/4" Plywood Floor Sheathing (132 Sheets of 4'x8') | 3,842 | 10% | 4,226 | SF | \$ | - |
| 76                           | 1/2" Plywood Roof Sheathing (133 Sheets of 4'x8')  | 3,864 | 10% | 4,250 | SF | \$ | - |
| 77                           | 1/2" Plywood Wall Sheathing (156 Sheets of 4'x8')  | 4,524 | 10% | 4,976 | SF | \$ | - |

|                         |     |      |      |
|-------------------------|-----|------|------|
|                         |     |      |      |
|                         |     |      |      |
| SUB TOTAL               |     | \$ - | \$ - |
| OVERHEAD & PROFIT (25%) | 25% | \$ - | \$ - |
| TOTAL BID               |     | \$ - | \$ - |